MISCELLANEOUS DEPARTMENTS.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Notification dated 15th August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore, up to 2 P.M. on 8th September 1933, for "Improvements to the Laboratory Buildings in the Chief Electrical Engineer's Office Compound, Bangalore."—

1. The tenders will be opened in public at 2 P.M. on 8th September 1933. The work should be completed within two months; and the monthly progress should not be less than Rs. 2,000.

2. The plan, detailed estimates and the conditions may be seen at the Office of the Chief Electrical Engineer, Bangalore, on all working days during the Office working hours.

3. The tenders should be accompanied by a statement in the form attached, showing the rates at which different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money and be superscribed "Tenders for Improvements to the Laboratory Buildings in the Chief Electrical Engineer's Office compound" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender the successful tenderer will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board of the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money of rejected tenders will be returned.

9. The construction work should be started within a week from the date of notification of acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

12. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Statement of quantities for Improvements to Laboratory Buildings in the Chief Electrical Engineer's Office premises, Bangalore.

Sl. No.	Items of work	Unit	Transformer building room	Lean to room of old stores	Hall adjoining the transformer workshop
1	Removing the existing corrugated iron sheet roofing with bolts and nuts, etc., complete and stacking the same.	Sqr.	40·00	12·80	...
2	G. I. Ridge sheet 22 B. W. G. 2 ft. wide fixed with new bolts nuts and lead washers, etc., complete.	Rft.	100·00	...	...
3	Roofing with new corrugated galvd. iron sheet 24 B. W. G. with galvd. iron bolts and nuts and lead washers, etc., complete with an overlap of 1 foot at ends and 3 corrugations at sides.	Sqr.	40·00	...	...
4	Teakwood wrought and put up with 2 coats of wood oiling including binding the same to rail purlins by hoop iron at intervals.	C.ft.	28·5	...	...
5	Ceiling with Teakwood planks ½" thick tongued and grooved and fixed on to purlins with screws including the bead-	Sqr.	32·00	..	...

Sl. No.	Items of work	Unit	Transformer building room	Lean to room of old stores	Hall adjoining transformer workshop
6	White and colour washing 2 coats including petty repairs to plaster, damages here and there.	Sqr.	73·00	131·25	50·00
7	Painting with silver grey silicate paint 2 coats including scraping of old paint where necessary.	„	45·00	27·00	3·00
8	Removing the existing windows and fixing the same in new positions with lintels, etc., including dismantling and building up of masonry, plaster, etc., complete.	..	...	No. 4	...
9	Removing doors and inserting the same in new places including filling up their spaces with masonry or window as the case may be, and finishing with plaster, etc., complete.	..	...	No. 3	...
10	Dismantling the existing masonry including cement concrete racks for insertion of a door 6' x 8' with lintels, etc., and fixing up the same with necessary masonry, complete.	...	..	1 Item	...
11	Removing the existing window 4' x 6' for inserting a door 3½' x 7½' including dismantling and building up of masonry with plaster, etc., complete.	...	...	1 Item	...
12a	Earthwork excavation for foundation and disposal of excess earth.	C.yd.	...	7·6	....
b	Stone masonry in clay foundation and basement including through stones fixed at 6'—0" intervals in every course.	C.ft.	...	204	...
c	Burnt brick in mortar superstructure ...	„	...	634	...
d	Stone slabs 6" thick roughly dressed and fixed in mortar.	S.ft.	...	160	20·00
13a	Doors: teakwood with panelled shutters and accessory fittings complete as per existing ones.	„	...	56	...
b	Fixing expanded metal to outside of windows as per existing works.	„	...	88	...
14a	Rolled steel work new fixed complete (Tata make).	Cwts.	...	20	27·71
b	Rolled old steel work fixed	„	...	7·3	..
c	Digging holes in walls and fixing bearing slabs, rafters, etc., in mortar.	Each	...	13	..
d	Roofing with old corrugated G. I. sheets with new Galvd. iron bolts and nuts and lead washers, etc., with overlap of 3 corrugation at sides and 1'—0" at ends.	Sqr.	...	12·80	...
e	Binding wall 9" x 9" on top of roofing built in brick in mortar with plaster, white wash, etc., complete.	Rft.	...	19	...
f	Six inches plain cornice brick in mortar with plaster, complete.	„	...	19	...
g	Chunam border 6" x 6" built in brick in mortar with plaster, etc., complete.	„	...	19	...
h	Removing the existing top roof to fecilitate fixing bottom roof and re-doing the same after the latter is fixed.	..	...	1 Item	...
15	Chunam plastering two coats ...	Sqr.	...	14·25	2·00
16	Supporting roof for dismantling walls ...	...	...	...	1 Item
17	Dismantling masonry and removing the debris to a distant place.	Cft.	..	...	271
18	Old bricks in new mortar	„	...	...	93

Abstract Notification dated 3rd August 1933.

The attention of the public is invited to the detailed notification, dated the 3rd August 1933, calling for tenders for extending the Office of the Superintendent, Power and Lighting, Bangalore, published in pages 1019 and 1020 of Part VI of the *Mysore Gazette*, dated 10th August 1933.

The latest date for receiving tenders is 25th August 1933.

C. M. CARIAPA,
Chief Electrical Engineer.

MYSORE STATE TROOPS, BANGALORE.

Notice, dated 18th August 1933.

Sealed tenders are invited for the supply of the undermentioned Miscellaneous articles required for the Mysore Military Stores during the official year 1933-34.

2. Tenders should be addressed to the Chief Commandant, Mysore State Troops, and superscribed "Tenders for the supply of Miscellaneous articles to Mysore Military Stores."

3. Tenders will be received at the Chief Commandant's Office, till 2 P.M. on Monday, the 4th September 1933, after which no tender will be received.

4. Tenders should clearly show the rate at which the articles delivered free at the Mysore Military Stores, Hebbal, Bangalore.

5. Every tender should be accompanied with a deposit of Rs. 25 in currency notes. If the tender is accepted and the tenderer fails to undertake the contract, he will forfeit the amount and the order cancelled immediately. If the tender is not accepted the amount will be returned to the tenderer.

6. The name of the successful tenderer will be notified in due course on the notice board of the Chief Commandant's Office and he will be required to deposit as security an amount equal to 5 per cent of the value of the order, and to execute an agreement for the due fulfilment of the contract for the supply required.

7. The Superintendent, Mysore Military Stores, will indent on the contractor for such of the articles named below as may be required from time to time, which should be supplied to him within the time specified therein; the receipt obtained for such supplies being submitted with the bill once a month to the Superintendent for check and countersignature.

8. The quantity noted in the Schedule are only approximate and not guaranteed and the quantity to be purchased may be more or less. The contract will be deemed to be limited to the quantity to be actually drawn.

9. No application from the contractors for any enhancement of the prices accepted due to whatsoever causes will be entertained during the period of contract.

10. Should the contractor fail to comply with any of the conditions detailed above, the contract will be forthwith cancelled and the deposit credited to Government.

11. The Chief Commandant reserves to himself the right to accepting or rejecting any tender without assigning any reason therefor.

12. Samples of these articles may be seen at the Office of the Superintendent, Military Stores, Hebbal, Bangalore, and counter samples furnished along with the tenders.

Schedule of articles required.

Note :—Rates to be quoted for free delivery at the Mysore Military Stores, Hebbal, Bangalore.

1	Badges Shoulder	...	Pairs	600	3rd Bn., Pattern with Roman III.
2	Brushes, boot ...	...		500	
3	Buttons, bone ...	...	Doz.	2,000	
4	Buttons, simplex ...	...	Gross	20	
5	Canes, Malaca with oval head one double-headed eagle and inscription 1st Bn.	...		200	
6	Clamps, brass, for kit bags ..	..		400	
7	Eyelets, brass ..	..	Doz.	300	
8	Football bladder No. 6 ..	..	"	12	
9	Do do ...	...		12	
10	Hemp rolls, pymore, big size ...	..		60	
11	Knives clasp with lanyard ...	..		50	

A. J. DONNE,
For *Chief Commandant.*